



NOTES:

1. LIMITS SHOWN ARE MAXIMUM ALLOWED AND MINIMUM REQUIRED FOR EXCAVATION AND BACKFILL.
2. UPPER PAY LIMITS FOR TRENCH EXCAVATION IS TOP OF EXISTING SURFACE, AT TIME OF TRENCH EXCAVATION.
3. UPPER PAY LIMITS FOR ROCK EXCAVATION IS TOP SURFACE OF ROCK.
4. UPPER PAY LIMIT FOR BACKFILL IS BOTTOM OF TEMPORARY PAVEMENT (IF USED), OR FINISH SURFACE IF BACKFILL IS PLACED UP TO FINISHED SURFACE AS NOTED ON THE DRAWINGS.
5. TEMPORARY OR PERMANENT BLOCKS OR ANY OTHER TYPE OF PIPE SUPPORT ARE NOT TO BE USED DURING PIPE INSTALLATION.

STORM SEWER TRENCH DETAIL

N.T.S.

ISSUE DATE: AUGUST 2012

REVISIONS		TOWN OF BATAVIA
DATE	COMMENTS	HIGHWAY & STORM SEWER DETAILS
		STORM SEWER TRENCH DETAIL
		DRAWING HS-22