



**NOTES:**

- 1) STAINLESS STEEL INSERTS SHALL BE USED AT ALL PE CONNECTIONS.
- 2) SADDLE AND CORPORATION STOP SHALL BE PLACED AT 22-1/2 DEGREES FROM HORIZONTAL IF IT WILL BE USED AS A SERVICE LOCATION.
- 3) IMMEDIATELY PRIOR TO THE WATER DEPARTMENT PLACING THE WATER MAIN IN SERVICE, CONTRACTOR SHALL REMOVE ALL COMPONENTS ASSOCIATED WITH TEMPORARY FACILITIES (i.e. SAMPLING TAPS, ETC.). THE CORPORATION STOP SHALL BE PLACED IN THE CLOSED POSITION AND THE QUICK CONNECT COUPLING PLUGGED IF THE LOCATION IS NOT USED AS A WATER SERVICE.
- 4) THE WATER MAIN SHALL BE DISINFECTED EQUAL TO AWWA STANDARD FOR DISINFECTING WATER MAINS DESIGNATION C651. FOLLOWING DISINFECTION, THE WATER MAIN SHALL BE FLUSHED UNTIL THE CHLORINE CONCENTRATION IN THE WATER LEAVING THE MAIN IS NO HIGHER THAN THAT GENERALLY PREVAILING IN THE SYSTEM. THE SAMPLING POINT(S) MUST BE DECONTAMINATED BY FLAMING.
- 5) FIRE HYDRANTS ARE NOT ACCEPTABLE SAMPLING POINTS.
- 6) THE WATER MAIN SHALL NOT BE PLACED INTO SERVICE UNTIL SO AUTHORIZED BY THE GENESEE COUNTY HEALTH DEPARTMENT.
- 7) REFER TO MATERIAL LIST, W-03.

## TEMPORARY DISINFECTION/BLOW-OFF/ SAMPLING TAP

N.T.S.

|                       |      |   |
|-----------------------|------|---|
| ISSUE DATE: JUNE 2015 |      | TOWN OF BATAVIA                                     |
|                       |      | WATER DETAILS                                       |
| REVISIONS             | DATE | COMMENTS  |
|                       |      |   |
|                       |      |   |
|                       |      |   |
|                       |      |   |
|                       |      | TEMPORARY<br>DISINFECTION/BLOW-OFF/<br>SAMPLING TAP |
|                       |      | DRAWING W-06  |